



COIMBATORE CITY MUNICIPAL CORPORATION
QUOTATION NOTICE

ROC.NO. 4200 /2021/MD5

DATED: 22-11-2021

Sub: Coimbatore City Municipal Corporation - Engineering Section - Calling for invites sealed quotations from local firm - Regarding

Ref: The Board of Directors of Coimbatore Smart City Limited dated.16-11-2021

Above the reference cited, The Managing Director approved on 20.11.2021 Coimbatore invites sealed quotations from local firm for the following work. The sealed quotations shall be addressed to "The Commissioner, Coimbatore City Municipal Corporation, Coimbatore, Big Bazaar Street, Coimbatore-641 001" and should reach this office on or before 3:00 PM on 24.11.2021.

Sr. No	Name of the Work
1	Supply ,Testing and Commissioning of Architectural outer front side and East Side Lighting System for Victoria Town Hall at Corporation Main Office
2	Supply and Installation of (Mini) Toilet (500 Sqf)
3	Supply and Installation of Urinal (10 x 5 = 50 Sqf) Mid Size

NOTE:

- 1) The firms are expected to quote their rates inclusive of GST if any
- 2) Payments will be made only after satisfactory completion of the installation work in all respects as per the certification by the departmental engineers

(Sd)
Executive Engineer
Coimbatore Corporation

// True copy-Forwarded by order//

Signature

COIMBATORE CITY MUNICIPAL CORPORATION

Quotation -Form

Name of work : Supply Testing and Commissioning of Architectual outer front side and East Side lighting System for Victoria Town Hall at Corporation Main Office in Ward No. 82 Central Zone.

Date : 24.12.2021

Item No.	Probable Quantity		Description of Work	Amount Figures
	Figure	Unit		Rs.P
1	9000	Days	Cost of Supply for 34 Nos of Four Feet mid Power With less than 70W RGB Liner grazing fixture with Elliptical 10 x 50 beam angle, 7 nos of four feet low power with less than 30 W RGBW Liner grazing fixture along with Elliptical 28 " x 84 " or Wide 120 " Beam angles. 1 No of two Feet low power with less than 15 W RGB Liner grazing fixture along with Elliptical 28 " x 84 " or wide 120 " Beam angles , 27 Nos of 5 Ft Factory Made Male to female Jumper cable , 8 Nos of 50 Ft factory made female leader cable, 4 Nos low Power with less than 18W RGB Spot Light Along with 4 Nos of Lens trim , 1 no of data formatting device and one no of DMX Controller for the Entire Site	
2	900	Days	Cost of Supply for Flexible CAT6 Cable 3 x 2.5 Sqmm Flexible Copper cable , 4 x 2.5 Sqmm flexible copper cable , HDPE Pipe for supply and data Cable , 4 KVA Stabilizer, Surge Protection device , IP 66 Rate Cable Junction Box, Gland , U Clamp, and 1 KVA UPS with 15 min Power backup, Electrical Panel, and Customized linear mesh as per site requirement	
			Sub TOTAL	
			GST 18 %	
			TOTAL	

Signature